

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の平均気温より求めた)

【高松】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.6	6.3	9.4	14.7	19.8	23.3	27.7	29.0	24.8	19.5	13.4	8.0
2	5.7	6.4	9.5	14.9	19.9	23.4	27.9	28.9	24.6	19.3	13.2	7.8
3	5.6	6.4	9.6	15.1	20.1	23.6	28.0	28.8	24.5	19.1	13.0	7.7
4	5.6	6.5	9.8	15.3	20.2	23.7	28.1	28.7	24.3	18.9	12.8	6.6
5	5.6	6.5	9.9	15.5	20.2	23.9	28.2	28.6	24.2	18.7	12.7	6.5
6	5.6	6.6	10.1	15.7	20.3	24.1	28.3	28.5	24.0	18.5	12.5	6.5
7	5.6	6.7	10.2	15.8	20.4	24.2	28.5	28.3	23.8	18.3	12.3	6.4
8	5.6	6.8	10.4	16.1	20.5	24.4	28.6	28.2	23.6	18.1	12.0	6.4
9	5.5	7.0	10.5	16.2	20.6	24.5	28.7	28.1	23.4	17.9	11.7	6.4
10	5.5	7.1	10.7	16.4	20.7	24.6	28.8	28.0	23.3	17.8	11.5	6.3
11	5.4	7.2	10.9	16.6	20.8	24.7	28.8	27.9	23.1	17.6	11.3	6.3
12	5.4	7.2	11.1	16.7	20.9	24.9	28.9	27.8	23.0	17.4	11.1	6.2
13	5.4	7.3	11.4	16.9	21.1	25.1	28.9	27.6	22.8	17.2	11.0	6.2
14	5.4	7.4	11.5	17.1	21.2	25.2	29.0	27.5	22.6	17.0	10.8	6.1
15	5.5	7.5	11.7	17.2	21.4	25.4	29.0	27.4	22.4	16.8	10.6	6.1
16	5.5	7.6	11.9	17.3	21.5	25.5	29.1	27.3	22.2	16.7	10.4	6.0
17	5.6	7.7	12.0	17.5	21.7	25.7	29.2	27.2	22.0	16.5	10.2	6.0
18	5.6	7.9	12.2	17.6	21.8	25.8	29.2	27.0	21.8	16.3	10.1	6.0
19	5.6	8.1	12.3	17.8	21.9	26.0	29.2	26.8	21.6	16.1	9.8	6.0
20	5.6	8.4	12.4	17.9	22.0	26.1	29.3	26.7	21.4	15.9	9.7	6.0
21	5.6	8.6	12.6	18.1	22.1	26.3	29.3	26.5	21.3	15.6	9.5	6.0
22	5.6	8.7	12.7	18.3	22.2	26.4	29.3	26.3	21.1	15.4	9.3	5.9
23	5.6	8.8	12.9	18.5	22.3	26.6	29.4	26.2	21.0	15.2	9.2	5.9
24	5.6	8.9	13.1	18.7	22.4	26.7	29.4	26.0	20.8	14.9	9.0	5.8
25	5.7	9.0	13.3	18.9	22.5	26.9	29.3	25.8	20.7	14.7	8.9	5.8
26	5.9	9.0	13.5	19.0	22.6	27.0	29.3	25.7	20.5	14.5	8.8	5.7
27	6.0	9.0	13.7	19.2	22.7	27.2	29.3	25.5	20.3	14.3	8.6	5.7
28	6.1	9.1	14.0	19.4	22.8	27.3	29.3	25.4	20.1	14.1	8.5	5.7
29	6.1	9.2	14.1	19.5	23.0	27.5	29.2	25.2	19.9	13.9	8.3	5.7
30	6.2	—	14.3	19.7	23.1	27.6	29.1	25.1	19.7	13.7	8.1	5.7
31	6.3	—	14.5	—	23.2	—	29.1	25.0	—	13.5	—	5.7

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の平均気温より求めた)

【多度津】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.9	6.3	9.2	14.1	19.0	22.5	27.0	28.5	24.6	19.4	13.5	8.3
2	5.9	6.4	9.3	14.3	19.2	22.6	27.1	28.4	24.5	19.2	13.3	8.2
3	5.9	6.5	9.4	14.5	19.3	22.8	27.2	28.4	24.4	19.0	13.2	8.0
4	5.8	6.5	9.5	14.7	19.4	22.9	27.4	28.3	24.2	18.8	12.9	7.9
5	5.8	6.5	9.7	14.9	19.5	23.1	27.5	28.2	24.1	18.6	12.8	7.9
6	5.8	6.6	9.8	15.1	19.6	23.2	27.6	28.1	23.9	18.4	12.6	7.8
7	5.8	6.7	9.9	15.2	19.7	23.4	27.7	28.0	23.7	18.2	12.4	7.7
8	5.8	6.8	10.1	15.4	19.7	23.5	27.9	27.9	23.5	18.1	12.2	7.7
9	5.8	7.0	10.2	15.6	19.8	23.7	28.0	27.8	23.3	17.9	11.9	7.7
10	5.7	7.1	10.4	15.8	19.9	23.8	28.1	27.7	23.2	17.7	11.7	7.6
11	5.6	7.1	10.6	15.9	20.1	23.9	28.2	27.6	23.0	17.5	11.5	7.6
12	5.6	7.2	10.8	16.1	20.2	24.1	28.2	27.5	22.8	17.3	11.3	7.4
13	5.6	7.2	11.0	16.2	20.3	24.2	28.3	27.4	22.7	17.1	11.1	7.4
14	5.6	7.4	11.1	16.4	20.5	24.4	28.4	27.3	22.5	17.0	11.0	7.3
15	5.6	7.4	11.3	16.5	20.6	24.5	28.4	27.2	22.3	16.8	10.7	7.3
16	5.7	7.5	11.5	16.7	20.8	24.7	28.5	27.1	22.1	16.6	10.6	7.2
17	5.7	7.7	11.6	16.8	20.9	24.8	28.5	26.9	21.9	16.5	10.4	7.1
18	5.8	7.8	11.8	16.9	21.0	24.9	28.6	26.8	21.7	16.3	10.3	7.2
19	5.8	8.0	11.9	17.1	21.1	25.1	28.6	26.6	21.5	16.1	10.1	7.2
20	5.8	8.2	12.0	17.2	21.3	25.2	28.7	26.5	21.3	15.9	9.9	7.2
21	5.8	8.4	12.1	17.4	21.4	25.4	28.7	26.3	21.2	15.7	9.7	7.2
22	5.8	8.5	12.3	17.6	21.4	25.6	28.8	26.2	21.0	15.4	9.5	7.1
23	5.8	8.6	12.4	17.8	21.5	25.7	28.8	26.0	20.8	15.2	9.4	6.9
24	5.8	8.7	12.6	18.0	21.6	25.9	28.8	25.8	20.7	15.0	9.3	6.8
25	5.8	8.8	12.8	18.2	21.7	26.0	28.8	25.7	20.5	14.8	9.2	6.7
26	6.0	8.8	13.0	18.3	21.9	26.2	28.8	25.5	20.4	14.6	9.0	6.6
27	6.0	8.9	13.2	18.5	22.0	26.3	28.8	25.4	20.2	14.4	8.9	6.5
28	6.1	8.9	13.4	18.6	22.1	26.5	28.7	25.2	20.0	14.2	8.8	6.5
29	6.2	9.0	13.6	18.8	22.2	26.7	28.7	25.1	19.8	14.0	8.6	6.6
30	6.3	—	13.8	18.9	22.3	26.8	28.7	25.0	19.6	13.8	8.4	6.6
31	6.3	—	13.9	—	22.4	—	28.6	24.8	—	13.7	—	6.1

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の平均気温より求めた)

【滝宮】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	4.1	4.8	8.0	13.4	18.4	22.1	26.6	27.4	23.0	17.6	11.6	6.4
2	4.2	4.9	8.1	13.6	18.5	22.3	26.7	27.3	22.9	17.4	11.4	6.3
3	4.1	5.0	8.2	13.8	18.7	22.4	26.8	27.3	22.7	17.2	11.2	6.1
4	4.1	5.0	8.4	14.0	18.8	22.6	26.9	27.2	22.6	16.9	11.0	6.0
5	4.1	5.1	8.6	14.2	18.9	22.8	27.0	27.0	22.4	16.8	10.9	6.0
6	4.1	5.2	8.7	14.4	19.0	23.0	27.1	26.9	22.3	16.6	10.7	5.9
7	4.1	5.3	8.8	14.5	19.1	23.1	27.2	26.8	22.0	16.4	10.5	5.8
8	4.1	5.4	9.0	14.7	19.1	23.3	27.3	26.7	21.8	16.2	10.3	5.8
9	4.1	5.6	9.2	14.9	19.2	23.4	27.4	26.6	21.6	16.0	10.0	5.8
10	4.0	5.7	9.3	15.1	19.3	23.5	27.5	26.5	21.5	15.8	9.7	5.8
11	4.0	5.8	9.5	15.3	19.5	23.7	27.6	26.3	21.3	15.7	9.5	5.7
12	4.0	5.8	9.8	15.4	19.6	23.8	27.6	26.2	21.2	15.4	9.4	5.6
13	4.0	5.9	10.0	15.6	19.8	24.0	27.6	26.1	21.0	15.3	9.2	5.5
14	4.0	6.0	10.2	15.7	19.9	24.2	27.7	25.9	20.8	15.1	9.0	5.4
15	4.0	6.1	10.3	15.9	20.0	24.3	27.7	25.8	20.6	14.9	8.8	5.4
16	4.1	6.2	10.5	16.0	20.2	24.5	27.7	25.7	20.4	14.8	8.6	5.3
17	4.2	6.3	10.7	16.1	20.4	24.6	27.8	25.6	20.2	14.6	8.5	5.2
18	4.2	6.5	10.8	16.3	20.5	24.8	27.8	25.4	20.0	14.5	8.4	5.3
19	4.2	6.7	11.0	16.4	20.6	24.9	27.8	25.2	19.8	14.2	8.2	5.3
20	4.2	6.9	11.1	16.6	20.7	25.0	27.8	25.1	19.6	14.0	8.0	5.3
21	4.2	7.1	11.2	16.8	20.8	25.2	27.9	24.9	19.4	13.8	7.8	5.3
22	4.2	7.3	11.4	16.9	20.9	25.3	27.9	24.7	19.3	13.5	7.7	5.2
23	4.2	7.4	11.6	17.1	21.0	25.5	27.9	24.5	19.1	13.3	7.5	5.0
24	4.2	7.5	11.7	17.3	21.2	25.6	27.9	24.3	18.9	13.1	7.4	4.9
25	4.3	7.5	11.9	17.5	21.3	25.8	27.9	24.2	18.8	12.9	7.3	4.8
26	4.5	7.6	12.2	17.7	21.4	25.9	27.8	24.0	18.6	12.7	7.1	4.6
27	4.6	7.7	12.4	17.8	21.5	26.1	27.8	23.8	18.4	12.5	7.0	4.5
28	4.6	7.7	12.6	18.0	21.7	26.2	27.7	23.7	18.2	12.3	6.9	4.5
29	4.7	7.8	12.8	18.2	21.8	26.4	27.7	23.5	18.0	12.1	6.7	4.5
30	4.8	—	13.0	18.3	21.9	26.5	27.6	23.4	17.8	11.9	6.6	4.5
31	4.8	—	13.2	—	22.0	—	27.5	23.2	—	11.7	—	4.2

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の平均気温より求めた)

【引田】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.1	5.8	8.4	13.7	18.5	22.0	26.3	27.4	23.8	18.9	13.1	7.7
2	5.2	5.8	8.5	13.9	18.6	22.2	26.4	27.3	23.7	18.7	12.9	7.6
3	5.2	5.9	8.6	14.1	18.7	22.3	26.5	27.2	23.5	18.5	12.8	7.4
4	5.1	5.9	8.8	14.2	18.8	22.5	26.6	27.2	23.4	18.3	12.6	7.3
5	5.1	6.0	9.0	14.4	18.9	22.6	26.7	27.1	23.3	18.1	12.5	7.2
6	5.1	6.1	9.1	14.6	19.0	22.8	26.8	27.0	23.1	18.0	12.3	7.1
7	5.1	6.2	9.2	14.8	19.1	23.0	26.9	26.9	22.9	17.8	12.0	7.1
8	5.1	6.3	9.3	15.0	19.2	23.1	27.0	26.8	22.7	17.6	11.8	7.1
9	5.0	6.5	9.5	15.1	19.2	23.2	27.1	26.7	22.6	17.4	11.5	7.1
10	5.0	6.6	9.7	15.3	19.4	23.4	27.2	26.7	22.5	17.2	11.3	7.0
11	4.9	6.6	9.9	15.4	19.5	23.5	27.3	26.6	22.3	17.1	11.1	6.9
12	4.9	6.7	10.1	15.6	19.6	23.7	27.3	26.5	22.2	16.9	10.9	6.8
13	4.9	6.7	10.4	15.7	19.8	23.8	27.3	26.3	22.0	16.7	10.7	6.7
14	4.9	6.8	10.5	15.9	19.9	24.0	27.4	26.3	21.8	16.5	10.5	6.7
15	5.0	6.9	10.7	16.1	20.0	24.1	27.4	26.2	21.6	16.4	10.3	6.6
16	5.0	6.9	10.8	16.2	20.2	24.3	27.5	26.1	21.5	16.2	10.1	6.5
17	5.1	7.0	11.0	16.3	20.3	24.4	27.5	26.0	21.3	16.1	10.0	6.5
18	5.1	7.2	11.2	16.5	20.4	24.6	27.5	25.8	21.1	15.9	9.8	6.5
19	5.1	7.4	11.3	16.6	20.5	24.7	27.5	25.7	20.9	15.7	9.6	6.5
20	5.1	7.6	11.4	16.8	20.7	24.9	27.6	25.5	20.7	15.5	9.4	6.6
21	5.1	7.8	11.5	16.9	20.7	25.0	27.6	25.4	20.6	15.3	9.2	6.5
22	5.1	7.9	11.7	17.1	20.9	25.2	27.6	25.3	20.4	15.1	9.1	6.4
23	5.1	8.0	11.9	17.3	21.0	25.3	27.6	25.1	20.3	14.8	9.0	6.1
24	5.1	8.1	12.1	17.5	21.1	25.4	27.6	24.9	20.1	14.6	8.9	6.0
25	5.2	8.2	12.2	17.6	21.2	25.6	27.6	24.8	20.0	14.4	8.7	5.9
26	5.4	8.2	12.5	17.8	21.3	25.7	27.6	24.6	19.8	14.2	8.6	5.8
27	5.4	8.2	12.7	17.9	21.4	25.8	27.6	24.5	19.7	14.0	8.4	5.7
28	5.5	8.2	12.9	18.1	21.5	26.0	27.6	24.4	19.5	13.8	8.3	5.6
29	5.6	8.3	13.1	18.2	21.7	26.1	27.5	24.3	19.3	13.6	8.1	5.6
30	5.7	—	13.3	18.4	21.8	26.2	27.5	24.1	19.1	13.4	7.9	5.6
31	5.7	—	13.5	—	21.9	—	27.4	24.0	—	13.2	—	5.1

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の平均気温より求めた)

【財田】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	4.1	4.9	7.9	13.2	18.3	22.0	26.5	27.3	23.1	17.7	11.8	6.5
2	4.1	5.0	8.0	13.4	18.4	22.2	26.6	27.3	23.0	17.5	11.6	6.3
3	4.1	5.1	8.1	13.6	18.5	22.3	26.7	27.2	22.8	17.3	11.4	6.2
4	4.1	5.1	8.3	13.8	18.6	22.5	26.8	27.1	22.7	17.1	11.3	6.1
5	4.1	5.2	8.5	14.0	18.7	22.7	26.9	27.0	22.5	16.9	11.1	6.0
6	4.0	5.3	8.6	14.2	18.8	22.8	27.0	26.8	22.4	16.7	11.0	5.9
7	4.0	5.4	8.7	14.3	18.9	23.0	27.1	26.7	22.1	16.5	10.7	5.9
8	4.0	5.6	8.9	14.5	19.0	23.1	27.2	26.6	21.9	16.3	10.5	5.9
9	4.0	5.7	9.1	14.7	19.1	23.3	27.3	26.5	21.7	16.1	10.2	5.9
10	3.9	5.8	9.3	14.9	19.2	23.4	27.3	26.5	21.6	15.9	9.9	5.8
11	3.9	5.9	9.5	15.0	19.3	23.6	27.4	26.3	21.4	15.8	9.7	5.7
12	3.9	5.9	9.7	15.2	19.5	23.7	27.4	26.2	21.3	15.6	9.5	5.6
13	3.9	6.0	9.9	15.4	19.6	23.9	27.5	26.1	21.1	15.4	9.4	5.6
14	3.9	6.1	10.1	15.6	19.8	24.0	27.5	25.9	20.9	15.2	9.2	5.5
15	4.0	6.2	10.2	15.7	20.0	24.2	27.5	25.8	20.7	15.1	9.0	5.4
16	4.0	6.3	10.4	15.8	20.1	24.3	27.6	25.7	20.5	14.9	8.8	5.3
17	4.1	6.4	10.6	15.9	20.3	24.5	27.6	25.6	20.3	14.8	8.7	5.3
18	4.1	6.5	10.8	16.1	20.4	24.7	27.6	25.4	20.1	14.6	8.5	5.3
19	4.2	6.8	10.9	16.2	20.5	24.8	27.7	25.3	19.9	14.4	8.3	5.4
20	4.2	7.0	11.0	16.4	20.6	24.9	27.7	25.1	19.7	14.2	8.1	5.4
21	4.2	7.2	11.1	16.6	20.7	25.1	27.7	24.9	19.5	14.0	7.9	5.3
22	4.1	7.4	11.3	16.7	20.8	25.2	27.7	24.7	19.4	13.7	7.8	5.2
23	4.1	7.5	11.5	16.9	21.0	25.4	27.7	24.6	19.2	13.5	7.6	5.0
24	4.1	7.5	11.7	17.1	21.1	25.5	27.7	24.4	19.1	13.2	7.5	4.9
25	4.3	7.6	11.9	17.3	21.2	25.6	27.7	24.2	18.9	13.0	7.4	4.7
26	4.4	7.6	12.1	17.5	21.3	25.8	27.7	24.0	18.7	12.8	7.3	4.5
27	4.5	7.6	12.3	17.6	21.4	25.9	27.7	23.9	18.5	12.6	7.2	4.4
28	4.6	7.7	12.6	17.8	21.6	26.1	27.6	23.8	18.3	12.5	7.0	4.3
29	4.7	7.8	12.8	18.0	21.7	26.2	27.6	23.6	18.1	12.3	6.8	4.4
30	4.8	—	12.9	18.1	21.8	26.3	27.5	23.4	17.9	12.1	6.7	4.3
31	4.8	—	13.1	—	21.9	—	27.4	23.3	—	11.9	—	3.8

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の平均気温より求めた)

【内海】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.6	6.1	8.8	13.8	18.5	22.1	26.3	27.8	24.2	19.2	13.5	8.2
2	5.7	6.2	8.9	14.0	18.6	22.2	26.4	27.8	24.0	19.0	13.4	8.1
3	5.6	6.2	9.0	14.2	18.7	22.3	26.5	27.7	23.8	18.8	13.2	7.9
4	5.6	6.3	9.2	14.3	18.8	22.5	26.7	27.6	23.7	18.6	13.0	7.7
5	5.6	6.3	9.4	14.5	18.9	22.6	26.8	27.6	23.6	18.4	12.9	7.6
6	5.5	6.4	9.5	14.7	19.0	22.8	26.9	27.5	23.4	18.2	12.7	7.5
7	5.5	6.5	9.6	14.9	19.1	22.9	27.0	27.4	23.2	18.0	12.5	7.4
8	5.5	6.6	9.8	15.0	19.1	23.1	27.1	27.3	23.1	17.9	12.2	7.4
9	5.5	6.7	9.9	15.2	19.2	23.2	27.2	27.2	22.9	17.7	11.9	7.3
10	5.4	6.8	10.1	15.4	19.3	23.3	27.3	27.1	22.8	17.6	11.7	7.2
11	5.4	6.9	10.3	15.5	19.5	23.5	27.4	27.0	22.6	17.4	11.5	7.1
12	5.3	6.9	10.5	15.7	19.6	23.6	27.5	26.9	22.5	17.2	11.4	7.0
13	5.3	7.0	10.7	15.8	19.8	23.8	27.5	26.8	22.3	17.0	11.2	7.0
14	5.3	7.1	10.8	16.0	19.9	23.9	27.6	26.7	22.1	16.8	11.0	6.9
15	5.4	7.2	11.0	16.1	20.1	24.1	27.7	26.6	21.9	16.7	10.8	6.8
16	5.4	7.3	11.2	16.2	20.2	24.2	27.7	26.5	21.7	16.5	10.6	6.6
17	5.5	7.4	11.3	16.3	20.3	24.4	27.8	26.4	21.6	16.4	10.5	6.6
18	5.5	7.5	11.5	16.5	20.5	24.5	27.8	26.2	21.4	16.2	10.3	6.5
19	5.5	7.8	11.6	16.6	20.6	24.6	27.9	26.1	21.2	16.0	10.1	6.4
20	5.5	8.0	11.7	16.7	20.7	24.8	27.9	25.9	21.0	15.8	9.9	6.4
21	5.5	8.2	11.8	16.9	20.8	24.9	27.9	25.8	20.9	15.6	9.7	6.3
22	5.5	8.3	12.0	17.1	20.9	25.1	28.0	25.6	20.7	15.4	9.6	6.2
23	5.5	8.4	12.1	17.3	21.0	25.2	28.0	25.5	20.6	15.1	9.4	6.1
24	5.5	8.5	12.3	17.4	21.1	25.4	28.0	25.3	20.4	14.9	9.3	6.0
25	5.6	8.5	12.5	17.6	21.2	25.5	28.0	25.1	20.3	14.7	9.2	6.0
26	5.7	8.6	12.7	17.8	21.3	25.6	28.0	25.0	20.1	14.5	9.0	5.9
27	5.8	8.6	12.9	17.9	21.4	25.8	28.0	24.9	19.9	14.4	8.9	5.8
28	5.9	8.6	13.1	18.1	21.6	25.9	28.0	24.7	19.7	14.2	8.7	5.8
29	6.0	8.7	13.3	18.2	21.7	26.1	28.0	24.6	19.5	14.0	8.6	5.7
30	6.0	—	13.5	18.4	21.8	26.2	27.9	24.5	19.4	13.8	8.4	5.7
31	6.0	—	13.6	—	21.9	—	27.9	24.3	—	13.7	—	5.6