

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の移動平均より求めた)

【測定地点：高松】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.7	6.3	9.4	14.7	19.7	23.4	27.7	28.9	24.8	19.5	13.4	8.0
2	5.6	6.4	9.6	14.9	19.9	23.5	27.8	28.8	24.6	19.3	13.2	7.9
3	5.6	6.5	9.7	15.1	20.0	23.6	28.0	28.7	24.5	19.1	13.0	7.8
4	5.6	6.5	9.8	15.3	20.1	23.8	28.1	28.6	24.3	18.9	12.8	7.7
5	5.6	6.6	10.0	15.5	20.2	23.9	28.2	28.5	24.1	18.7	12.6	7.5
6	5.6	6.7	10.1	15.6	20.3	24.0	28.3	28.4	24.0	18.5	12.4	7.4
7	5.5	6.8	10.3	15.8	20.4	24.2	28.4	28.3	23.8	18.3	12.2	7.3
8	5.5	6.9	10.4	16.0	20.5	24.3	28.5	28.2	23.6	18.1	12.0	7.2
9	5.5	7.0	10.6	16.2	20.6	24.5	28.6	28.1	23.5	18.0	11.8	7.1
10	5.5	7.1	10.8	16.4	20.8	24.6	28.7	28.0	23.3	17.8	11.6	7.0
11	5.5	7.2	10.9	16.5	20.9	24.8	28.8	27.9	23.1	17.6	11.4	7.0
12	5.5	7.3	11.1	16.7	21.0	24.9	28.8	27.8	22.9	17.4	11.2	6.9
13	5.5	7.4	11.3	16.9	21.1	25.1	28.9	27.6	22.7	17.2	11.0	6.8
14	5.5	7.5	11.5	17.0	21.2	25.2	29.0	27.5	22.6	17.0	10.8	6.7
15	5.5	7.6	11.6	17.2	21.4	25.4	29.0	27.4	22.4	16.8	10.6	6.6
16	5.5	7.7	11.8	17.3	21.5	25.5	29.1	27.2	22.2	16.6	10.4	6.6
17	5.5	7.9	12.0	17.5	21.6	25.7	29.1	27.1	22.0	16.4	10.2	6.5
18	5.6	8.0	12.1	17.7	21.7	25.8	29.2	26.9	21.8	16.2	10.1	6.4
19	5.6	8.1	12.3	17.8	21.9	26.0	29.2	26.8	21.7	16.0	9.9	6.3
20	5.6	8.3	12.5	18.0	22.0	26.1	29.2	26.6	21.5	15.8	9.7	6.3
21	5.7	8.4	12.6	18.2	22.1	26.3	29.2	26.5	21.3	15.6	9.5	6.2
22	5.7	8.5	12.8	18.3	22.2	26.4	29.2	26.3	21.1	15.4	9.4	6.1
23	5.7	8.7	13.0	18.5	22.3	26.6	29.3	26.2	21.0	15.2	9.2	6.1
24	5.8	8.8	13.2	18.7	22.4	26.7	29.3	26.0	20.8	15.0	9.1	6.0
25	5.8	8.9	13.3	18.8	22.5	26.9	29.2	25.9	20.6	14.8	8.9	5.9
26	5.9	9.0	13.5	19.0	22.6	27.0	29.2	25.7	20.4	14.6	8.8	5.9
27	6.0	9.1	13.7	19.2	22.7	27.2	29.2	25.5	20.2	14.4	8.6	5.8
28	6.0	9.2	13.9	19.3	22.9	27.3	29.1	25.4	20.1	14.2	8.5	5.8
29	6.1	9.3	14.1	19.5	23.0	27.4	29.1	25.2	19.9	14.0	8.3	5.8
30	6.2	—	14.3	19.6	23.1	27.6	29.0	25.1	19.7	13.8	8.2	5.7
31	6.2	—	14.5	—	23.2	—	29.0	24.9	—	13.6	—	5.7

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の移動平均より求めた)

【測定地点：多度津】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.9	6.4	9.2	14.1	19.0	22.6	26.9	28.5	24.6	19.4	13.5	8.3
2	5.9	6.4	9.4	14.3	19.1	22.7	27.1	28.4	24.5	19.2	13.3	8.2
3	5.9	6.5	9.5	14.5	19.2	22.8	27.2	28.3	24.3	19.0	13.1	8.1
4	5.9	6.6	9.6	14.7	19.3	23.0	27.3	28.2	24.2	18.8	12.9	8.0
5	5.8	6.6	9.7	14.9	19.4	23.1	27.4	28.1	24.0	18.6	12.7	7.9
6	5.8	6.7	9.9	15.0	19.6	23.2	27.6	28.1	23.8	18.5	12.5	7.8
7	5.8	6.8	10.0	15.2	19.7	23.4	27.7	28.0	23.7	18.3	12.3	7.7
8	5.8	6.9	10.2	15.4	19.8	23.5	27.8	27.9	23.5	18.1	12.1	7.6
9	5.7	6.9	10.3	15.6	19.9	23.6	27.9	27.8	23.3	17.9	11.9	7.5
10	5.7	7.0	10.5	15.7	20.0	23.8	28.0	27.7	23.2	17.7	11.7	7.4
11	5.7	7.1	10.6	15.9	20.1	23.9	28.1	27.6	23.0	17.5	11.6	7.3
12	5.7	7.2	10.8	16.0	20.2	24.1	28.2	27.5	22.8	17.3	11.4	7.2
13	5.7	7.3	10.9	16.2	20.4	24.2	28.2	27.4	22.6	17.2	11.2	7.2
14	5.7	7.4	11.1	16.4	20.5	24.4	28.3	27.2	22.4	17.0	11.0	7.1
15	5.7	7.5	11.3	16.5	20.6	24.5	28.4	27.1	22.3	16.8	10.8	7.0
16	5.7	7.7	11.4	16.7	20.7	24.7	28.4	27.0	22.1	16.6	10.6	6.9
17	5.7	7.8	11.6	16.8	20.9	24.8	28.5	26.9	21.9	16.4	10.4	6.8
18	5.7	7.9	11.7	17.0	21.0	25.0	28.5	26.7	21.7	16.2	10.3	6.8
19	5.8	8.0	11.9	17.1	21.1	25.1	28.6	26.6	21.5	16.0	10.1	6.7
20	5.8	8.1	12.0	17.3	21.2	25.3	28.6	26.4	21.4	15.9	9.9	6.6
21	5.8	8.3	12.2	17.5	21.3	25.4	28.7	26.3	21.2	15.7	9.8	6.5
22	5.8	8.4	12.4	17.6	21.4	25.6	28.7	26.2	21.0	15.5	9.6	6.5
23	5.9	8.5	12.5	17.8	21.5	25.7	28.7	26.0	20.8	15.3	9.5	6.4
24	5.9	8.6	12.7	17.9	21.6	25.9	28.7	25.9	20.7	15.1	9.3	6.3
25	6.0	8.7	12.9	18.1	21.8	26.0	28.7	25.7	20.5	14.9	9.2	6.3
26	6.0	8.8	13.0	18.3	21.9	26.2	28.7	25.5	20.3	14.7	9.0	6.2
27	6.1	8.9	13.2	18.4	22.0	26.3	28.7	25.4	20.1	14.5	8.9	6.2
28	6.1	9.0	13.4	18.6	22.1	26.5	28.6	25.2	19.9	14.3	8.7	6.1
29	6.2	9.1	13.6	18.7	22.2	26.6	28.6	25.1	19.8	14.1	8.6	6.1
30	6.2	—	13.8	18.8	22.3	26.8	28.6	24.9	19.6	13.9	8.5	6.0
31	6.3	—	13.9	—	22.4	—	28.5	24.8	—	13.7	—	6.0

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の移動平均より求めた)

【測定地点：滝宮】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	4.2	4.9	8.1	13.4	18.4	22.2	26.5	27.4	23.0	17.6	11.6	6.5
2	4.2	4.9	8.2	13.6	18.5	22.3	26.7	27.3	22.9	17.4	11.4	6.3
3	4.1	5.0	8.3	13.8	18.6	22.5	26.8	27.2	22.7	17.2	11.2	6.2
4	4.1	5.1	8.4	14.0	18.7	22.6	26.9	27.1	22.5	17.0	11.0	6.1
5	4.1	5.2	8.6	14.1	18.8	22.8	27.0	27.0	22.4	16.8	10.8	6.0
6	4.1	5.3	8.7	14.3	19.0	22.9	27.1	26.9	22.2	16.6	10.6	5.9
7	4.1	5.4	8.9	14.5	19.1	23.1	27.2	26.8	22.0	16.4	10.4	5.8
8	4.1	5.4	9.1	14.7	19.2	23.2	27.2	26.7	21.8	16.2	10.2	5.7
9	4.1	5.5	9.2	14.9	19.3	23.4	27.3	26.6	21.7	16.0	10.0	5.6
10	4.1	5.6	9.4	15.0	19.4	23.5	27.4	26.4	21.5	15.8	9.8	5.5
11	4.1	5.7	9.6	15.2	19.5	23.7	27.5	26.3	21.3	15.7	9.6	5.4
12	4.1	5.8	9.8	15.4	19.7	23.8	27.5	26.2	21.1	15.5	9.4	5.3
13	4.1	6.0	9.9	15.5	19.8	24.0	27.6	26.0	20.9	15.3	9.3	5.3
14	4.1	6.1	10.1	15.7	19.9	24.1	27.6	25.9	20.8	15.1	9.1	5.2
15	4.1	6.2	10.3	15.8	20.0	24.3	27.7	25.8	20.6	14.9	8.9	5.1
16	4.1	6.3	10.5	16.0	20.2	24.4	27.7	25.6	20.4	14.7	8.7	5.0
17	4.1	6.4	10.6	16.2	20.3	24.6	27.7	25.5	20.2	14.5	8.5	5.0
18	4.2	6.6	10.8	16.3	20.4	24.7	27.8	25.3	20.0	14.4	8.4	4.9
19	4.2	6.7	11.0	16.5	20.6	24.9	27.8	25.2	19.8	14.2	8.2	4.8
20	4.2	6.8	11.1	16.6	20.7	25.0	27.8	25.0	19.6	14.0	8.0	4.7
21	4.3	7.0	11.3	16.8	20.8	25.2	27.8	24.9	19.5	13.8	7.9	4.7
22	4.3	7.1	11.5	17.0	20.9	25.3	27.8	24.7	19.3	13.6	7.7	4.6
23	4.3	7.2	11.7	17.1	21.1	25.5	27.8	24.5	19.1	13.3	7.6	4.6
24	4.4	7.4	11.8	17.3	21.2	25.6	27.8	24.4	18.9	13.1	7.4	4.5
25	4.4	7.5	12.0	17.5	21.3	25.8	27.8	24.2	18.7	12.9	7.3	4.4
26	4.5	7.6	12.2	17.6	21.4	25.9	27.7	24.0	18.5	12.7	7.1	4.4
27	4.5	7.7	12.4	17.8	21.5	26.0	27.7	23.9	18.4	12.5	7.0	4.3
28	4.6	7.8	12.6	17.9	21.7	26.2	27.6	23.7	18.2	12.3	6.9	4.3
29	4.7	7.9	12.8	18.1	21.8	26.3	27.6	23.5	18.0	12.1	6.7	4.3
30	4.7	—	13.0	18.2	21.9	26.4	27.5	23.4	17.8	12.0	6.6	4.2
31	4.8	—	13.2	—	22.1	—	27.5	23.2	—	11.8	—	4.2

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の移動平均より求めた)

【測定地点：引田】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.2	5.8	8.5	13.7	18.4	22.1	26.3	27.3	23.8	18.9	13.1	7.8
2	5.2	5.9	8.6	13.8	18.5	22.2	26.4	27.3	23.7	18.7	12.9	7.6
3	5.1	5.9	8.8	14.0	18.7	22.4	26.5	27.2	23.5	18.5	12.7	7.5
4	5.1	6.0	8.9	14.2	18.8	22.5	26.6	27.1	23.4	18.3	12.5	7.4
5	5.1	6.1	9.0	14.4	18.9	22.7	26.7	27.1	23.2	18.2	12.3	7.3
6	5.1	6.2	9.1	14.6	19.0	22.8	26.8	27.0	23.1	18.0	12.1	7.1
7	5.1	6.2	9.3	14.7	19.1	22.9	26.9	26.9	22.9	17.8	11.9	7.0
8	5.0	6.3	9.4	14.9	19.2	23.1	27.0	26.8	22.8	17.6	11.7	6.9
9	5.0	6.4	9.6	15.1	19.3	23.2	27.0	26.7	22.6	17.4	11.5	6.8
10	5.0	6.5	9.8	15.2	19.4	23.4	27.1	26.6	22.4	17.3	11.3	6.7
11	5.0	6.6	9.9	15.4	19.5	23.5	27.2	26.5	22.3	17.1	11.1	6.6
12	5.0	6.7	10.1	15.6	19.7	23.7	27.2	26.4	22.1	16.9	10.9	6.5
13	5.0	6.8	10.3	15.7	19.8	23.8	27.3	26.3	22.0	16.7	10.7	6.4
14	5.0	6.9	10.5	15.9	19.9	24.0	27.3	26.2	21.8	16.5	10.6	6.3
15	5.0	7.0	10.6	16.0	20.0	24.1	27.4	26.1	21.6	16.4	10.4	6.3
16	5.0	7.1	10.8	16.2	20.1	24.3	27.4	26.0	21.4	16.2	10.2	6.2
17	5.1	7.2	11.0	16.3	20.3	24.4	27.5	25.9	21.3	16.0	10.0	6.1
18	5.1	7.3	11.1	16.5	20.4	24.6	27.5	25.8	21.1	15.8	9.8	6.0
19	5.1	7.4	11.3	16.7	20.5	24.7	27.5	25.6	20.9	15.6	9.7	5.9
20	5.1	7.5	11.5	16.8	20.6	24.9	27.5	25.5	20.8	15.4	9.5	5.9
21	5.2	7.6	11.6	17.0	20.7	25.0	27.5	25.4	20.6	15.2	9.3	5.8
22	5.2	7.8	11.8	17.1	20.9	25.1	27.6	25.2	20.4	15.0	9.2	5.7
23	5.2	7.9	12.0	17.3	21.0	25.3	27.6	25.1	20.3	14.8	9.0	5.6
24	5.3	8.0	12.1	17.4	21.1	25.4	27.6	25.0	20.1	14.6	8.8	5.6
25	5.3	8.1	12.3	17.6	21.2	25.5	27.6	24.8	19.9	14.4	8.7	5.5
26	5.4	8.2	12.5	17.7	21.3	25.7	27.5	24.7	19.8	14.2	8.5	5.4
27	5.4	8.2	12.7	17.9	21.4	25.8	27.5	24.5	19.6	14.0	8.4	5.4
28	5.5	8.3	12.9	18.0	21.6	25.9	27.5	24.4	19.4	13.8	8.2	5.3
29	5.6	8.4	13.1	18.2	21.7	26.0	27.5	24.2	19.3	13.6	8.1	5.3
30	5.6	—	13.3	18.3	21.8	26.2	27.4	24.1	19.1	13.5	7.9	5.3
31	5.7	—	13.5	—	22.0	—	27.4	24.0	—	13.3	—	5.2

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の移動平均より求めた)

【測定地点：財田】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	4.1	4.9	8.0	13.2	18.2	22.1	26.4	27.3	23.1	17.7	11.8	6.5
2	4.1	5.0	8.1	13.4	18.3	22.2	26.5	27.2	23.0	17.5	11.6	6.4
3	4.1	5.1	8.3	13.6	18.4	22.4	26.6	27.1	22.8	17.3	11.4	6.3
4	4.0	5.2	8.4	13.8	18.6	22.5	26.7	27.0	22.6	17.1	11.2	6.2
5	4.0	5.3	8.5	14.0	18.7	22.7	26.8	26.9	22.5	16.9	11.0	6.0
6	4.0	5.4	8.7	14.2	18.8	22.8	26.9	26.8	22.3	16.7	10.8	5.9
7	4.0	5.4	8.8	14.3	18.9	23.0	27.0	26.7	22.1	16.5	10.6	5.8
8	4.0	5.5	9.0	14.5	19.1	23.1	27.1	26.6	22.0	16.3	10.4	5.7
9	4.0	5.6	9.2	14.7	19.2	23.3	27.2	26.5	21.8	16.2	10.2	5.6
10	4.0	5.7	9.3	14.8	19.3	23.4	27.2	26.4	21.6	16.0	10.0	5.5
11	4.0	5.8	9.5	15.0	19.4	23.6	27.3	26.3	21.4	15.8	9.8	5.4
12	4.0	5.9	9.7	15.2	19.5	23.7	27.4	26.2	21.2	15.6	9.6	5.3
13	4.0	6.1	9.9	15.3	19.7	23.9	27.4	26.0	21.0	15.4	9.4	5.3
14	4.0	6.2	10.0	15.5	19.8	24.0	27.5	25.9	20.9	15.3	9.2	5.2
15	4.0	6.3	10.2	15.7	19.9	24.2	27.5	25.8	20.7	15.1	9.0	5.1
16	4.0	6.4	10.4	15.8	20.1	24.3	27.5	25.6	20.5	14.9	8.9	5.0
17	4.1	6.5	10.5	16.0	20.2	24.5	27.6	25.5	20.3	14.7	8.7	4.9
18	4.1	6.7	10.7	16.1	20.3	24.6	27.6	25.4	20.1	14.5	8.5	4.8
19	4.1	6.8	10.9	16.3	20.5	24.8	27.6	25.2	19.9	14.3	8.3	4.8
20	4.1	6.9	11.0	16.5	20.6	24.9	27.6	25.0	19.7	14.1	8.2	4.7
21	4.2	7.0	11.2	16.6	20.7	25.1	27.7	24.9	19.6	13.9	8.0	4.6
22	4.2	7.2	11.4	16.8	20.8	25.2	27.7	24.7	19.4	13.7	7.9	4.6
23	4.3	7.3	11.6	16.9	21.0	25.3	27.7	24.6	19.2	13.5	7.7	4.5
24	4.3	7.4	11.7	17.1	21.1	25.5	27.6	24.4	19.0	13.3	7.5	4.4
25	4.4	7.5	11.9	17.3	21.2	25.6	27.6	24.2	18.8	13.1	7.4	4.4
26	4.4	7.6	12.1	17.4	21.3	25.8	27.6	24.1	18.7	12.9	7.3	4.3
27	4.5	7.7	12.3	17.6	21.4	25.9	27.6	23.9	18.5	12.7	7.1	4.3
28	4.6	7.8	12.5	17.7	21.6	26.0	27.5	23.8	18.3	12.5	7.0	4.2
29	4.7	7.9	12.7	17.9	21.7	26.2	27.5	23.6	18.1	12.3	6.8	4.2
30	4.7	—	12.9	18.0	21.8	26.3	27.4	23.4	17.9	12.1	6.7	4.2
31	4.8	—	13.1	—	22.0	—	27.4	23.3	—	12.0	—	4.1

# コンクリートの打ち込みから28日までの期間の平均気温

(2008年から2017年の移動平均より求めた)

【測定地点：内海】

月 日	1月	2月	3月	4月	5月	6月	7月	8月	9月	10月	11月	12月
1	5.7	6.1	8.9	13.8	18.4	22.1	26.3	27.8	24.1	19.2	13.5	8.3
2	5.6	6.2	9.0	14.0	18.5	22.2	26.4	27.7	24.0	19.0	13.3	8.1
3	5.6	6.2	9.2	14.2	18.6	22.4	26.5	27.6	23.8	18.8	13.1	8.0
4	5.6	6.3	9.3	14.3	18.8	22.5	26.6	27.6	23.7	18.6	13.0	7.9
5	5.6	6.4	9.4	14.5	18.9	22.6	26.8	27.5	23.5	18.4	12.8	7.7
6	5.5	6.5	9.5	14.7	19.0	22.8	26.9	27.4	23.4	18.3	12.6	7.6
7	5.5	6.5	9.7	14.8	19.1	22.9	27.0	27.3	23.2	18.1	12.4	7.5
8	5.5	6.6	9.8	15.0	19.2	23.1	27.1	27.3	23.1	17.9	12.2	7.4
9	5.5	6.7	10.0	15.2	19.3	23.2	27.2	27.2	22.9	17.7	12.0	7.3
10	5.4	6.8	10.2	15.3	19.4	23.3	27.3	27.1	22.7	17.6	11.8	7.2
11	5.4	6.9	10.3	15.5	19.5	23.5	27.3	27.0	22.6	17.4	11.6	7.1
12	5.4	7.0	10.5	15.6	19.7	23.6	27.4	26.9	22.4	17.2	11.4	7.0
13	5.4	7.1	10.6	15.8	19.8	23.8	27.5	26.8	22.2	17.0	11.2	6.9
14	5.4	7.2	10.8	15.9	19.9	23.9	27.6	26.6	22.1	16.8	11.0	6.9
15	5.4	7.3	11.0	16.1	20.0	24.1	27.6	26.5	21.9	16.7	10.8	6.8
16	5.4	7.4	11.1	16.2	20.2	24.2	27.7	26.4	21.7	16.5	10.7	6.7
17	5.4	7.5	11.3	16.4	20.3	24.3	27.7	26.3	21.6	16.3	10.5	6.6
18	5.5	7.6	11.4	16.5	20.4	24.5	27.8	26.1	21.4	16.1	10.3	6.5
19	5.5	7.8	11.6	16.7	20.6	24.6	27.8	26.0	21.2	15.9	10.1	6.4
20	5.5	7.9	11.7	16.8	20.7	24.8	27.9	25.9	21.1	15.7	10.0	6.4
21	5.5	8.0	11.9	17.0	20.8	24.9	27.9	25.7	20.9	15.6	9.8	6.3
22	5.6	8.1	12.1	17.1	20.9	25.1	27.9	25.6	20.7	15.4	9.6	6.2
23	5.6	8.2	12.2	17.3	21.0	25.2	27.9	25.5	20.6	15.2	9.5	6.1
24	5.6	8.3	12.4	17.4	21.1	25.3	27.9	25.3	20.4	15.0	9.3	6.1
25	5.7	8.4	12.6	17.6	21.3	25.5	27.9	25.2	20.2	14.8	9.2	6.0
26	5.7	8.5	12.7	17.7	21.4	25.6	27.9	25.0	20.1	14.6	9.0	5.9
27	5.8	8.6	12.9	17.9	21.5	25.8	27.9	24.9	19.9	14.4	8.9	5.9
28	5.8	8.7	13.1	18.0	21.6	25.9	27.9	24.7	19.7	14.2	8.7	5.8
29	5.9	8.8	13.3	18.1	21.7	26.0	27.9	24.6	19.5	14.0	8.6	5.8
30	6.0	—	13.4	18.3	21.8	26.2	27.9	24.4	19.3	13.9	8.4	5.7
31	6.0	—	13.6	—	22.0	—	27.8	24.3	—	13.7	—	5.7